



SILT FENCE MUST BE
INSPECTED AND
MAINTAINED DAILY



TRENCH DETAIL

NOTES:

1. BOTTOM OF FILTER FABRIC FENCE MUST BE INSTALLED A MINIMUM OF 6" BELOW GRADE. BOTH ENDS OF EACH FENCE SECTION MUST EXTEND AT LEAST 8 FEET UPSLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.
2. ACCUMULATED SEDIMENT MUST BE INSPECTED AND REMOVED DAILY.
3. ANY FENCE SECTION, WHICH HAS BEEN UNDERMINED OR TOPPED, MUST BE IMMEDIATELY REPLACED.
4. WHERE ENDS OF FILTER FABRIC COME TOGETHER, THEY MUST BE OVERLAPPED, FOLDED AND STAPLED TO PREVENT SEDIMENT BYPASS. THE TOE ANCHOR MUST BE BACKFILLED AND COMPACTED TO A DENSITY EQUAL TO THE SURROUNDING SOILS.

		REVISIONS	MISSOURI AMERICAN WATER STANDARD CIVIL SILT FENCE DETAIL	
			MISSOURI AMERICAN WATER ST. LOUIS, MO. 63141	
			MISSOURI AMERICAN WATER ENGINEERING 727 CRAIG ROAD ST. LOUIS, MO. 63141  AMERICAN WATER DRAWN BY KKM PROJECT ENG'R APPROVED DATE 02-27-09 PROJECT IP USE DIMENSIONS ONLY SCALE N.T.S.	
			USE APPROVED DRAWINGS ONLY FOR CONSTRUCTION PURPOSES	0201-0601-SD68